

Executant 1967 sali motoare
 Investitie 1967 sali motoare
 Obiect 1967 sali motoare
 Deviz 2 electrice



Deviz analitic

Pozitie	Cod resursa	U/M	Cantitate	Sp.mat Sp.man Sp.uti	Pret materiale Pret manopera Pret utilaj Pret transport Nr.ore/UM Greutate/UM	Val. materiale Val. manopera Val. utilaj Val. transport TOTAL A Greutate totala
0	1	2	3		4	5

1	RPEE01D1	82 BUCATA	5,00000			
---	----------	-----------	---------	--	--	--

INLOC INTRERUPATOR MANUAL UNIPOLAR CONSTRUCTIE NOR

MALA APAR DIBL LEMN CUMPANA BACHELITA

L:12010 -0001:5519173 -INTRERUPTOR PACHET BIPOLAR SIMBOL 0520 25A ROTATIV

2	ED12B1	82 BUCATA	3,00000			
---	--------	-----------	---------	--	--	--

APARAT DE SEMNALIZARE OPTICA (INDICATOR POZITIE, CA
 SETA, LAMPA SEMNALIZ.)

L:12025 -0016:5537955 -CUTIE SEMNALIZARE OPTICA COD 4370

3	RPEE02F1	82 BUCATA	6,00000			
---	----------	-----------	---------	--	--	--

INLOC COMUTATOR SERIE UNIP APARENT CONSTR NORMALA

DIBLURI LEMN CUMPANA BACHELITA

L:12011 -0006:5520378 -COMUTATOR CRUCE CUMPANA PT.SIMBOL 024 10A 250V S/3185

4	RPEG02C1	82 BUCATA	3,00000	-100,00		
---	----------	-----------	---------	---------	--	--

INLOC TABL ELECT PE STELAJ MET MODULAT CU MASCA PE
 RTINAX PE PERETE SAU NISE SUPR < 0,91-1,50MP

5	8807126	BUCATA	3,00000			
---	---------	--------	---------	--	--	--

TABLOU ELECTRIC ARIANNE2

9sig.bip. aut..10A+16A+ 25A

6	EC14F1	82 BUCATA	1,00000			
---	--------	-----------	---------	--	--	--

CUTIE TERMIN.PT.INST COMANDA SEMNAL BLOCARI INCL.L
 EGATURA LA CLEME TABLOU SAU APARAT 49-61 CONDUCTE*

7	W1SC01A	99 BUCATA	1,00000			
---	---------	-----------	---------	--	--	--

PANOU, STELAJ, DULAP METALIC (PROTECTIE, COMANDA, MASU
 RA, SEMNALIZARE, SERVICII PROPRII, ETC) ECHIPAT

0	1	2	3	4	5
8	W1MD04A	99 BUCATA	10,00000		

SIR DE CLEME CONECTOR ELECTRIC DE 10-63A

L:W1ML003-0006:5537499 -CLEMA DE LEG 95MMP, 315A

9	W1MD05A	99 BUCATA	10,00000		
---	---------	-----------	----------	--	--

LEGAREA CONDUCTORULUI LA CIRCUITELE SECUNDARE INTR
E CUTIA TERMINALA SI SIRUL DE CLEME

10	W1ME02B	99 BUCATA	4,00000		
----	---------	-----------	---------	--	--

TRECERE IZOLATA INTERIOR-EXTERIOR PRIN PERETE, 20
KV

L:W1M006B-0006:5600662 -IZOLATOR SUPT ARMARE INT.II 12,50 125 20KV S 5852/2

L:W1M007G-0012:5211526 -CAPAC CI-3,75-125

L:W1M007I-0012:5211526 -CAPAC CI-3,75-125

L:W1M007J-0006:5211520 -ARMATURA INFERIOARA AS-12,5-125

L:W1ML008-0011:5201012 -BARA DE TRECERE BTB 20 CU, 1020A 2X30X5MM

11	RPED16A	99 M	175,00000		
----	---------	------	-----------	--	--

MONT.CABL.EL.SEMICOND.CU NUL DIN CUPRU,ARMAT.SIRMA
OL ZN.PT.TENS.3,5-6KV,ACMYHCSAIV, S=3X25+16MMP

L:EL03D -0038:7319369 -DOZE RAMIFICATIE BACHELITA PT.CABLU IPE 4 IESIRI

L:EL15E -0174:4817358 -CABLU CU IZOL MANT CAUC MCCGI 3 X 95+50 S 12220/6

12	RPEF11A05	82 BUCATA	54,00000		
----	-----------	-----------	----------	--	--

INLOC CORP ILUM PT LAMPI FLUORESCENTE TUBULARE TIP
CGA 240 2X40W DIBLURI LEMN FARA REFLECTOR

L:12009 -0071:5106043 -LAMPA MONOBLOC ILUM.SALI PUBL. CU RELEU STICLA COS P

13	RPEE03A3	82 BUCATA	15,00000		
----	----------	-----------	----------	--	--

INLOC PRIZA BIPOL INGROPAT CONSTR NORMALA BACHELIT
A DREPTUNGHULARA

14	RPEE03A4	82 BUCATA	60,00000 -100,00		
----	----------	-----------	------------------	--	--

INLOC PRIZA BIPOL INGROPAT CONSTR NORMALA AMINOPLA
ST DUBLA

15	7313039	BUCATI	30,00000		
----	---------	--------	----------	--	--

CUTIE CU 4 PRIZE MONTATE ST

0	1	2	3	4	5
16	7313041	BUCATI	30,00000		

CUTIE 3 PRIZE MONTATA ST

17	RPEB01C1	82 M	120,00000		
----	----------	------	-----------	--	--

INLOC CABLU ENERGI INST APARENT CU SCOABE PE CONS

FIXATE IN PERETE CABLU SECT < 4MMP

L:12007 -0022:4802688 -CABLU ENERGIE CYABY 0,6/ 1KV 3X 16 M S 8778

18	RPEB02A9	82 M	860,00000		
----	----------	------	-----------	--	--

INLOCUIRE COND DE CU FY IZOL SECT 4MMP INTROD IN TUB PVC, PEL, TEAVA

19	RPEB02A7	82 M	1250,00000		
----	----------	------	------------	--	--

INLOCUIRE COND DE CU FY IZOL SECT 1,5MMP INTROD IN TUB PVC, PEL, TEAVA

20	RPEB02A8	82 M	1858,00000		
----	----------	------	------------	--	--

INLOCUIRE COND DE CU FY IZOL SECT 2,5MMP INTROD IN TUB PVC, PEL, TEAVA

21	RPEA10E1	82 M	180,00000	-100,00	
----	----------	------	-----------	---------	--

INLOC TEAVA PVC TIP U DIAM EXT 50MM < 10M LUNG INS TALAT APARENT PE DIBLURI DE LEMN

22	3270072	M	180,00000		
----	---------	---	-----------	--	--

PAT CABLU 20X15

23	RPEA01D1	82 M	880,00000		
----	----------	------	-----------	--	--

INLOCUIRE TUB IZOLANT IP-PVC IN ZIDARIE TENC DIAME TRUL EXT 25 MM IN CANTITATI < 3M LUNGIME

24	RPCU17A5	82 M	880,00000		
----	----------	------	-----------	--	--

ASTUPAREA SANTURILOR IN ZIDARIE CU MORTAR DE IPSOS -VAR SI NISIP SANTUL AVIND SECT.DE 20-30 CMP

0	1	2	3	4	5
25	RPEI03B	99 M	126,00000		

INLOC.CIRC.PNEUM.AMCR, TV.CUPRU, AL, PVC CU D=12MM, IN
CL.PIESE DE RACORD., PROB.SI PUNEREA IN FUNCT.

L:EL03G	-0038:7319369	-DOZE RAMIFICATIE BACHELITA PT.CABLU IPE	4	IESIRI	
L:EL15F	-0174:4817358	-CABLU CU IZOL MANT CAUC MCCGI	3 X 95+50	S 12220/6	
26	RPEG20A1	82 BUCATA	3,00000		

DEMONTARE TABLOU DISTRIB METALIC*

27	EF02A1	82 BUCATA	1,00000		
----	--------	-----------	---------	--	--

TABLOU ELECTRIC PE SCHELET MET.CU MASCA MONT.PERET
E SAU IN NISA, TABLOUL CU SUPR.<0,30MP

L:12061	-0026:5500744	-CUTIE ETANSA INTRERUP. III 16A 380V	SIMBOL 7030.		
28	RPEG14A1	82 BUCATA	6,00000		

COMPLETARE TABLOU PE PLACA MARMORA CU UN CIRCUIT S
IGURANTA LS MONOFAZIC 25 A *

L:12001	-0057:4826907	-CONDUCTOR FY	1X 4	S 6865	
L:12015	-0001:5537228	-SOCLU PT.SIGURANTA CU LEGATURIIN FATA	LF25A	SIMB.2030	
29	RPED05E1	82 M	36,00000		

INLOC CABLU ENERG TRAS IN TUB METALIC PT RACORD LA
MOTOARE TABL APAR EXCLUS TUB PROT CABL SECT 35MMP
cablu alimentare CYABY 5x35

L:12007	-0030:4803113	-CABLU ENERGIE CYABY	0,6/ 1KV 4X 35	M S 8778	
30	RPEB04	91 M	128,00000		

CONDUCTORI PT.CURENTI SLABI TIP TY, FCH250 DE
1X0,5MMP SAU 2X0,84MMP SAU2X1,00MMP

L:12004	-0012:4831251	-CONDUCTOR TCYR	2X 1,2	S. 4037	
31	TRA01A10P	82 TONE	8,00000		

TRANSPORTUL RUTIER AL PAMINTULUI SAU MOLOZULUI CU
AUTOBASCULANTA DIST.=10 KM \$

32	TRA02A15	82 TONE	9,30000		
----	----------	---------	---------	--	--

TRANSPORTUL RUTIER AL MATERIALELOR, SEMIFABRICATELO
R CU AUTOCAMIONUL PE DIST.= 15 KM. \$

0	1	2	3	4	5
Greutate		9,362			
Total ore		1674,00			

Intocmit:

P.e.e. imp.

Jonitã deunitã

Lej

AVIZAT

Dir. gen. adm.

cdor.

Rodica Vasile Bododel.

VERIFICAT TEHNIC	
P.co	Ag. Sofia Patl
DATA	